

# Pune Sholapur Road Development Company Limited

**Regd. Office :** The IL&FS Financial Center, Plot C-22, G Block,  
Bandra Kurla Complex, Mumbai- 400051  
**Tel :** 022-26533333 **Fax :** 022-26523979  
**CIN :** U45203MH2009PLC195154

April 01, 2024

## Corrigendum-I

<b>S. No</b>	<b>Description</b>	<b>As per revised Documents/NIT</b>			
1	RFB – Volume 2 Execution of Major Maintenance works by Strengthening with DBM & BC Layers (MMR works) at various locations of service road at Pune Solapur Section of NH 9 from Km 144+400 to Km 249+000 in the State of Maharashtra (Annexure I, Part A – BOQ)	The quantities for items no 1 & 3 as per BOQ mentioned in Annexure I – Part A – BOQ as per RFB Volume 2 have been revised. Please consider the quantities as tabulated below:			
		<b>Sr. No.</b>	<b>Brief Description</b>	<b>Unit</b>	<b>Quantity</b>
		1	Providing and applying tack coat with cationic bitumen emulsion (RS1) using emulsion pressure distributor at the rate of 0.20- 0.30 kg per sqm on the prepared bituminous/granular surface cleaned with mechanical broom as per relevant clauses of section -503 of MoRTH specification.	Sqm	4,96,548
		3	Dense Graded Bituminous Macadam-II (Providing and laying dense graded bituminous macadam with higher capacity batch type HMP using crushed aggregates of specified grading, premixed with bituminous binder @ 4.5 per cent by weight of total mix and filler, transporting the hot mix to work site, laying with a hydrostatic paver finisher with sensor control to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MoRTH specification clause No. 505 complete in all respects)	Cum	3,294